



GENERAL NOTES:

1. PAVEMENT SHALL NOT BE OPENED WITHOUT FIRST RECEIVING A PERMIT FROM THE DEPARTMENT OF PUBLIC WORKS.
2. THE TRENCH SHALL BE BACKFILLED WITH AGGREGATE (CA-6 GRADATION) AND COMPACTED TO 95% OF THE STANDARD PROCTOR DENSITY. TRENCH SPOIL OR EXCAVATED MATERIAL SHALL BE DISPOSED OF BY THE CONTRACTOR AT THEIR EXPENSE.
3. PRIOR TO THE PLACING OF P.C. CONCRETE, THE EXPOSED EDGES OF ALL EXISTING PAVEMENT SHALL BE SAWCUT FULL DEPTH TO PROVIDE A SMOOTH, CLEAN VERTICAL EDGE, FREE OF LOOSE MATERIAL
4. EXCAVATIONS SHALL BE PROTECTED BY BARRICADES WITH FLASHING LIGHTS, AT LOCATIONS WHERE ADJUSTMENTS ARE LOCATED IN TRAVEL LANES, A ONE-INCH (1") STEEL PLATE SHALL BE PLACED AND MAINTAINED BY THE CONTRACTOR UNTIL THE SURFACE RESTORATION IS COMPLETE. THE PLATE SHALL BE PROTECTED FROM SLIDING AND TRANSITIONED WITH BITUMINOUS RAMPS AS REQUIRED. BARRICADES AND STEEL PLATES SHALL BE PRESENT AT THE WORK SITE PRIOR TO THE ROAD OPENING.
5. MINIMUM WIDTH OF A CONCRETE PATCH SHALL BE FULL CONCRETE PANELS.
6. DOWEL BASKETS ARE REQUIRED FOR MULTIPLE PANELS.
7. STREET OPENINGS SHALL BE RESTORED WITH COLD PATCH BEFORE THE END OF THE DAY AND MAINTAINED UNTIL SUCH TIME AS THE PERMANENT PATCH (CONCRETE OR HOT MIX ASPHALT, DEPENDING ON THE STREET) CAN BE INSTALLED PER SPECIFICATIONS BETWEEN APRIL 15 AND NOVEMBER 15.

REV.:	JKB	REV:	4-23-18
REV.:	DRG	REV:	4-18-17
REV.:	DRG	REV:	5-5-15
DRAWN BY:	VJGL	DATE:	2-16-98

**RIGID PAVEMENT
UTILITY TRENCH**

VILLAGE OF LOMBARD

PAVEMENT 10